

The Wrong Unit of Uncertainty: Simultaneous Conformal Bands for Repeated Cross-National Surveys

Kunwoo Park

Department of Politics, Kookmin University, Seoul, Republic of Korea

pkw31386094@gmail.com ORCID: 0009-0007-9067-8964

Abstract

Comparative research routinely reads one wave-pair contrast as a persistent, distribution-wide trend—attaching uncertainty to the wrong unit and over-detecting change. We give a deployable instrument: a finite-sample simultaneous band over a country’s whole attitude *trajectory*, with the country as the exchangeable unit and an ordered hierarchy of claims—exact at any K for the estimated trajectory, explicitly bounded for the latent one, and inside a selector whose nested fallbacks make the guarantee hold under any selection rule. In the ESS the hierarchy cuts a marginal reading of twenty of thirty countries to net decline in six. Over the full 2002–2024 record none certifies a persistent slide; reading every ordered contrast and both directions off one band, twenty-three of thirty-three countries certify both a fall and a rise, and span erosion certifies in eight. On the World Values Survey the same shift of rung cuts the certified set 1.9–4.8×; what survives is post-communist and Arab-Spring states. The second error—calibration on estimated objects—we resolve by scope: the correction is non-identified without the design-noise law and unreachable across countries, but at the

small-area unit of the same survey the frozen selector activates it, cutting the fallback band by 15–17% without losing coverage.

1 Introduction

Comparative politics increasingly treats a national public as a *distribution* rather than a mean. Trust in parliament in a country and year is a cumulative distribution function over a response scale. Repeated cross-national surveys—the European Social Survey (ESS; Kaminska and Lynn, 2017), the World Values Survey, the AmericasBarometer (Cohen et al., 2021), let us track how that distribution moves across waves and *transport* it: predict one country’s trajectory from the others. Conformal methods are a natural tool, promising finite-sample, distribution-free coverage.

Two wrong units. A claim and its calibration can each be attached to the wrong object. The *claim* “democratic trust is declining” is typically built from a single wave-pair mean contrast, then narrated as a country-level trend. Our instrument is a finite-sample simultaneous band over a country’s whole trajectory, with the country as the exchangeable unit, and an ordered hierarchy of claims: pairwise $\rightarrow$ any-pair $\rightarrow$ net $\rightarrow$ persistent $\rightarrow$ Bonferroni. The top rung is strictly stronger than the net-trend claim the literature typically intends, so we treat the two as co-headlines. This multiplicity-honest core needs no survey design and applies to any repeated distributional claim.

The second, subtler wrong unit is the calibration: the objects conformal transport calibrates on are themselves *estimated* from complex probability samples, and standard practice plugs them in as truth.

The two errors are distinct. Writing $F_{c,r}(t)$ for country c ’s latent CDF at threshold t in

wave r and $\tilde{F}_{c,r}(t)$ for its complex-survey estimate,

$$\tilde{F}_{c,r}(t) - \mu_r(t) = \underbrace{(F_{c,r}(t) - \mu_r(t))}_{\text{transport error}} + \underbrace{(\tilde{F}_{c,r}(t) - F_{c,r}(t))}_{\text{design error}}, \quad (1)$$

where μ_r is the transport center. A band calibrated on the observed $\tilde{F}$ scores treats the sum as the transport error alone: when the design error is non-negligible the band is too wide, yet any correction subtracting the survey noise can make it too narrow, being itself estimated from few countries.

Contributions. We make four. *First, a diagnosis and a portable instrument.* We separate the claim unit (a wave-pair contrast standing in for a distribution-wide trajectory) from the calibration unit (the omitted design-error layer of (1)), and give a finite-sample simultaneous band over a country’s whole trajectory with a multiplicity-honest guarantee hierarchy that corrects the first. *Second, a provably-valid deployed procedure.* The band we recommend is a clustered “population” conformal band, finite-sample exact at any K (Theorem 3), inside a selector whose validity does not depend on how it selects. Its two anchor branches are *nested*, and selection among nested bands anchored at an exact one is validity-free; the four target-blind gates are therefore an efficiency device, not a validity assumption (Theorem 5). We validate the frozen procedure in three disclosed layers, ending with a sealed run on six unseen DGP families. *Third, two named reanalyses* (Section 7) where the instrument changes the substantive picture. For European trust the hierarchy certifies net decline in six of thirty (2018–2024), not the twenty flagged marginally. Over the full 2002–2024 record no country certifies persistence, twenty-three of thirty-three certify both declines and recoveries, and eight certify span erosion, all read off one band at one level, by a claim-family transfer argument that removes the multiplicity and endpoint-selection corrections a per-rung construction needs. Globally, a wave-pair reading of the Foa–Mounk “deconsolidation” battery on the WVS/EVS (1981–2022) over-counts the persistent phenomenon by 2.6–6.5 $\times$.

Aggregating per-item certifications then turns the correction into a discovery: the thirteen-country *certified core* concentrates in post-communist and Arab-Spring-aftermath states. *Fourth, the scope condition that justifies this deployment, and where it ends.* Without the design-noise law the latent transport-error distribution is non-identified (Theorem 1). With it, the correction is still unreachable at cross-national scale: the measured design-to-total ratio stays severalfold below the level at which deconvolution helps, while the reliability diagnostic obeys an algorithmic floor $D \geq \sqrt{2/(K-1)}$ that requires $K \geq 94$ exchangeable populations. The two largest surveys fail in opposite ways: the WVS clears the size barrier ($K \approx 100$) with negligible design noise, the ESS has genuine clustered noise but $K \leq 33$. One unit down, on a region’s departure from its national distribution with $K \approx 230$ –290 regions, the frozen selector does activate it, and holding out whole countries confirms the region is the exchangeable unit (Section 6).

The remainder sets up the problem and the impossibility result (Section 2), builds the method and its theory (Sections 3–4), validates it (Section 5), characterizes the real-data regime (Section 6), reanalyzes political trust (Section 7), situates the contribution (Section 8) and discusses scope (Section 9).

2 Setup and the two targets

The object we deploy is the exact simultaneous band of Theorem 3; the impossibility below (Theorem 1) is a scope boundary delimiting when a design-aware correction to that band is even available.

Objects. We observe K source countries, indexed $c = 1, \dots, K$, treated as exchangeable units (the “population” or cluster is the exchangeable object, not the individual respondent). Each country has a latent attitude trajectory $F_{c,r}(t)$, a CDF over a fixed grid of thresholds $t \in \{t_1, \dots, t_T\}$ and survey rounds r . We do not see $F_{c,r}$; we see a complex-survey estimate $\tilde{F}_{c,r}(t) = F_{c,r}(t) + S_{c,r}(t)$, where $S_{c,r}$ is design (sampling) error with a design variance $v_{c,r}(t)^2$

that a stratified-PSU / replicate-weight bootstrap can estimate. Define the transport score of a country as its worst-case standardized deviation from the transport center,

$$R_c = \max_{r,t} \frac{|F_{c,r}(t) - \mu_r(t)|}{\sigma(t)}, \quad \tilde{R}_c = R_c + \xi_c,$$

where $\tilde{R}_c$ is the same quantity computed from the observed $\tilde{F}$ and ξ_c is the induced design contamination. (Because R is a supremum the additive centred score model is a working approximation, exact at the curve scale under (A1), whose failure direction is conservative for the plug-in band.) The governing scalar is the design-to-total SD ratio

$$\rho = \frac{\text{SD}(\xi)}{\text{SD}(\tilde{R})} = \sqrt{\frac{\overline{v^2}}{s_R^2 + \overline{v^2}}} \in [0, 1),$$

$\rho \rightarrow 0$ the design-noise-negligible regime, $\rho \rightarrow 1$ noise-dominated. (The simulations' generative dial is the unbounded $\text{SD}(\xi)/\text{SD}(R)$; reported ρ values use the bounded definition.)

Target and validity. We want a simultaneous band covering a new country's *latent* trajectory, $\Pr(F_{\text{new},r}(t) \in \hat{B}(r,t) \forall r,t) \geq 1 - \alpha$. Ordinary clustered conformal on the observed scores is exact for the *survey-estimate* target $\tilde{F}_{\text{new}}$, needing only exchangeability; its coverage of the latent target differs by an explicit gap that vanishes with the design-noise scale (Theorem 2(b); symmetry of the design law alone is not enough for conservativeness). Its width is inflated by design noise by a factor growing with ρ , and correcting that requires removing the design contribution, a deconvolution.

What country exchangeability assumes. The transport band's identifying assumption is a superpopulation postulate: participating countries' trajectory laws are symmetric draws, over a set that is not sampled, enters and exits rounds non-randomly, and changes designs across rounds. A strong idealization, tempered three ways. The headline certifications of Section 7 do not use it: they are within-country design-bootstrap statements. Under

approximate exchangeability the Barber et al. (2023) bound controls the coverage gap by an unobserved total-variation distance, which we treat as qualitative. And a leave-one-region-out audit finds near-nominal held-out coverage except for the post-communist East (6/9 and 5/9 at nominal 0.90)—a quantified scope condition on transport *into* that bloc (Supplementary Material).

The impossibility. The central obstruction is that the deconvolution is not identified from the contaminated scores alone.

Theorem 1 (Non-identification and necessity of design information). *Let the observed score be $\tilde{R} = R + \xi$ with $R \perp \xi$. (i) The law of R is not identified from the law of $\tilde{R}$ without restrictions on the law of ξ : there exist distinct pairs $(\mathcal{L}_R, \mathcal{L}_\xi) \neq (\mathcal{L}'_R, \mathcal{L}'_\xi)$ with $\mathcal{L}_R * \mathcal{L}_\xi = \mathcal{L}'_R * \mathcal{L}'_\xi$. (ii) Consequently, among non-randomized bands measurable in the observed scores alone, any band narrower than the $(\lceil(1 - \alpha)(K+1)\rceil - 1)$ -th order statistic of $\{|\tilde{R}_c|\}$ undercovers the latent target on the member $\xi \equiv 0$ of the class, which it cannot distinguish from the contaminated one. The only room below the plug-in radius is the conformal discreteness slack, which randomized smoothing exhausts; uniform improvement beyond it requires shrinking the class of admissible noise laws.*

The reading is constructive (proof in Appendix A): a band that is both valid and narrower than the plug-in must supply the design-noise law—replicate weights or a design bootstrap, exactly what Section 3 uses.

Remark 1 (Beyond surveys). Nothing here is survey-specific: the result holds whenever conformal calibration uses estimated objects: MRP small-area outputs, learned or imputed features, meta-analytic effects. Design/measurement information is the identifying ingredient, and its reliability at finite K is itself bounded (Proposition 1); confirmed outside surveys on a small-area calibration (Supplementary Material).

3 A nominal-safe adaptive method

Theorem 1 says the design bootstrap is the identifying input. The method turns that input into a band by choosing, target-blind, among three constructions and by never using the aggressive one unless it is provably reliable at the available number of countries.

Three branches. For calibration error curves $\{\tilde{E}_c\}_{c=1}^K$ over threshold grid t , with per-country design SD $\hat{v}_c(t)$ from the stratified-PSU bootstrap: (i) *Clustered PCB* takes the conformal quantile of the *unstudentized* scores $\max_t |\tilde{E}_c(t)|$ (the U0 construction): exact for the survey-estimate target at any K , with the latent gap of Theorem 2(b). (ii) *Deconvolution* studentizes by the finite- K -safe target scale $\hat{s}_T^2(t) = \max(s_{\text{plug}}^2(t) - [\bar{v}^2(t) - z \text{ SE}]_+, \text{ floor})$, which subtracts a *lower* confidence bound on the design variance so the correction cannot over-shrink; its width scales as $\sqrt{1 - \rho^2}$ relative to PCB. (iii) *Conservative* inflates each unstudentized score by the design SD, $\max_t (|\tilde{E}_c(t)| + z \hat{v}_c(t))$, a score that dominates the PCB score pointwise, so the conservative band *contains* the PCB band by construction. This nesting is load-bearing: selection between nested bands anchored at an exact band is validity-free, so the selector needs no conditional-coverage argument.

The three questions. A naive selector asks *can we deconvolve* and *do we need to*; the safe selector adds the missing third question, *can we do it safely at this K ?*

Safe selector (Algorithm 1). Let $\hat{\rho}_{\text{LCB}}$ be a conservative lower bound on ρ , $D = \max_t \text{SE}(\hat{s}_T^2) / \hat{s}_T^2$ a reliability diagnostic, and $\hat{\delta}_{\text{UCB}}(D)$ a frozen upper bound on the finite- K coverage remainder. Deconvolution is used *iff all four gates pass*: (A) $\hat{\rho}_{\text{LCB}} > \rho_0$ (design noise materially large); (B) $\hat{\delta}_{\text{UCB}}(D) \leq \delta_{\text{max}}$ (remainder within budget); (C) $\widehat{\text{Gain}} - \Delta_g > g_{\text{min}}$ (beats conservative by a margin); (D) stability. Otherwise the band is PCB when $\hat{\rho}_{\text{LCB}} \leq \rho_0$ and the conservative envelope when design noise is real but information insufficient. Every gate is a function of the calibration set only, so the selector is target-blind, and by Theorem 5's nested-band argument, validity survives even adversarial selection between the

Algorithm 1: Nominal-safe adaptive design-aware band

Input: calibration curves $\{\tilde{R}_c\}$ (unit = country), design replicates $\{\hat{v}_c\}$, target curve $\hat{F}_{\text{new}}$, level α ; frozen $\rho_0, \delta_{\max}, g_{\min}, \Delta_g$ and the K -only budget rule $\alpha_{\text{dec}}(K)$ set $(\alpha_{\text{anchor}}, \alpha_{\text{dec}})$ by the frozen budget rule (full α to the anchors when gate B is infeasible at this K);
compute diagnostics $s, \hat{s}_T, \hat{\rho}_{\text{LCB}}, D, \hat{\delta}_{\text{UCB}}(D)$; the nested unstudentized anchor radii $r_{\text{PCB}}, r_{\text{con}}$ at level α_{anchor} ; and r_{dec} at level α_{dec} ;
if $\hat{\rho}_{\text{LCB}} \leq \rho_0$ **then**
| branch $\leftarrow$ PCB;
else if $\hat{\delta}_{\text{UCB}}(D) \leq \delta_{\max}$ **and** *stable* **and** $\widehat{\text{Gain}} - \Delta_g > g_{\min}$ **then**
| branch $\leftarrow$ deconvolution;
else
| branch $\leftarrow$ conservative;
return $\hat{F}_{\text{new}} \pm r_{\text{branch}}$, branch, and diagnostics;

anchor branches. The deconvolution branch, which is not nested, is charged its own miss budget $\alpha_{\text{dec}} = \min\{\max(0.1\alpha, 3/(K+1)), \alpha/2\}$ (the anchors run at $\alpha - \alpha_{\text{dec}}$), and only in the $K \geq 94$ regime where its gate can open at all. At the K of every certification sample in this paper the anchors keep the full α and the deployed guarantee is exact. All constants are frozen before validation (Appendix B); when deconvolution is used the reported level is the observable $1 - \alpha - \hat{\delta}_{\text{UCB}}(D)$, a frozen *calibrated* bound (the theorem-level guarantee is Theorem 4's $\varepsilon_{K,B}$).

Deployment. The method ships as one call, `dapcb(cal_errors, v_cal, center, alpha)`, returning the band, selected branch, diagnostics, coverage level, and fallback reason, so the user sees why the band was built and reads off its finite- K guarantee.

4 Theory

We state validity for the oracle, the estimated-law procedure, and the deployed selector, then efficiency. Proofs are in Appendix A; each theorem has a machine-checked contract test.

Theorem 2 (Oracle validity). *Suppose the countries are exchangeable and the design law is*

known. (a) *The clustered band is finite-sample valid for the survey-estimate target: $\Pr(\tilde{F}_{new} \in \hat{B}) \geq 1 - \alpha$, using exchangeability only.* (b) *For the latent target the same band satisfies, for every $u > 0$, $\Pr(F_{new} \in \hat{B}) \geq 1 - \alpha - \Pr(\xi < -u) - \Pr(\tilde{R} \in (\hat{q} - u, \hat{q}])$: a noise-tail term plus a local anti-concentration term, vanishing with the design-noise scale ($\rho^{2/3}$ under variance-only tails, ρ up to logarithms under sub-Gaussian noise). Symmetric design noise alone does not make the band conservative here—a bimodal counterexample is in the Supplementary Material, which is why we report the observed ρ .* (c) *The deconvolution band with the true target scale is valid for the latent target—finite-sample exact under the scale-family assumption (A1)—with width a factor $\sqrt{1 - \rho^2} + o(1)$ of the clustered band.*

Theorem 3 (Exact finite- K validity of the deployed base band). *Let the base band use the unstudentized cluster score $R_c = \max_t |E_c(t)|$ (no data-dependent modulation), with a center satisfying the symmetric-construction condition (Appendix A states the four admissible cases). If the countries are exchangeable, then for every K the band $\hat{B} = \text{center} \pm \hat{q}$, with $\hat{q}$ the $[(1 - \alpha)(K+1)]$ -th order statistic of $\{R_c\}$, satisfies $\Pr(\tilde{F}_{new} \in \hat{B}) \geq [(1 - \alpha)(K+1)]/(K+1) \geq 1 - \alpha$, distribution-free, exact for the survey-estimate trajectory (T1); the latent trajectory (T2) adds the explicit gap of Theorem 2(b), bounded through the reported ρ . Two asymmetries are excluded by construction—in-sample modulation and grand-mean centers containing their own unit, at a width cost of $\leq 5\%$ on the near-homoskedastic real curves.*

Theorem 4 (Estimated-law validity). *Assume a common scale family indexed by the design variance (A1), anti-concentration of the sup-score law near its upper quantile (A2), and bounded curves with an unbiased size- B design bootstrap (A3); the appendix states all three precisely. Then (i) with oracle scales the deconvolution band is finite-sample exact for the latent target at every K , and (ii) with estimated scales it satisfies $\Pr(F_{new} \in \hat{B}) \geq 1 - \alpha - \varepsilon_{K,B}$ with $\varepsilon_{K,B} = O(\sqrt{\log(KT)/\min(K, B)})$, by a sandwich and concentration argument. The finite- K -safe scale $\hat{s}_T^2$ (Section 3) subtracts a lower confidence bound on the design variance, making the scale-error term one-sided (wide, not narrow) outside an α_2 -probability*

event. Some shape restriction is not removable—the bimodal counterexample of Theorem 2(b) defeats any latent-target band without one, and (A1) is one sufficient choice.

Theorem 5 (Safe-adaptive finite- K validity—the deployed pipeline). *Deploy Algorithm 1 with unstudentized PCB and conservative branches (scores $\max_t |E_c(t)|$ and $\max_t (|E_c(t)| + z\widehat{v}_c(t))$, both at level α_{anchor}) and the deconvolution branch at its own budget α_{dec} , where $(\alpha_{\text{anchor}}, \alpha_{\text{dec}}) = (\alpha, 0)$ when the reliability gate is infeasible at the observed K (Proposition 1: $K < 94$, which covers every certification sample analyzed in this paper, including the WVS ≥ 2 -wave sets at $K = 59$ –77) and otherwise $\alpha_{\text{dec}} = \min\{\max(0.1\alpha, 3/(K+1)), \alpha/2\}$ with $\alpha_{\text{anchor}} = \alpha - \alpha_{\text{dec}}$, a frozen function of K alone. Then, finite-sample and with no conditions on the selection rule,*

$$\Pr(\tilde{F}_{\text{new},r}(t) \in \widehat{B}) \geq 1 - \alpha \quad (K < 94), \quad \Pr(F_{\text{new},r}(t) \in \widehat{B}) \geq 1 - \alpha - \varepsilon_{K,B} \quad (K \geq 94).$$

The clauses name different targets because they rest on different assumptions: exchangeability alone gives the estimated trajectory T1 exactly (the latent T2 adding Theorem 2(b)’s gap), while (A1)–(A3), inherited from Theorem 4 through its remainder $\varepsilon_{K,B}$, which is attached to the deconvolution branch only, additionally deliver the latent target directly, by an anchor-domination lemma (Appendix A).

The proof uses no conditional-on-selection step: a nested-band lemma (the conservative score dominates the PCB score pointwise, and selection between nested bands anchored at an exact band is validity-free, an instance of nested-conformal machinery (Gupta et al., 2022; Yang and Kuchibhotla, 2024), our contribution being to engineer the branches so it applies) plus a union bound charging the non-nested branch its own budget where its gate can open. Two scope notes: at $K \geq 94$ the reported level $1 - \alpha - \widehat{\delta}_{\text{UCB}}(D)$ is a frozen calibrated bound, not a theorem; and leave-one-out centers carry a residual $O(1/K^2)$ asymmetry bounded only heuristically, so a strict guarantee wants a split-fold center.

Efficiency. The low- ρ deconvolution/PCB width ratio is $1 - \frac{1}{2}\rho^2 + O(\rho^4)$ (proved); conservative $\supseteq$ PCB holds pointwise; and selection cannot inflate miscoverage (Theorem 5). The remaining width results, one of them open, are in Appendix A.

5 Simulation and a design-preserving stress test

Simulation establishes two facts: attaching the band to the wrong unit collapses coverage, and the safe selector meets its guarantees on data it has never seen.

5.1 The wrong unit collapses coverage

On a ground-truth simulation ($K = 30$ countries, $T = 6$ thresholds, errors correlated across rounds and thresholds) we ask each band for *trajectory* coverage, the whole curve-path at once (Figure 1). All three bands are unstudentized and finite-sample, so only the score’s unit varies. A band that is marginally valid at the round level covers the trajectory 81.7% of the time at $L = 2$ and 49.8% at $L = 8$; per threshold the figures are 38.2% and 3.5%. Only the country-trajectory band holds its nominal 90% at every length, because the trajectory is a single exchangeable unit. This is the coverage face of the paper’s thesis, and the same mechanism drives the certification-count collapse of Section 7. Pre-registered, reported as produced (e28).

Severity: what each rung can detect. At ESS-like design noise (e32), 80% power at the *net* rung needs a per-pair decline of 0.02–0.03 CDF points (realistic secular erosion), while the *persistent* rung needs 0.06–0.08, crisis-scale, and its power *falls* as the trajectory lengthens. Injecting known declines into the real ESS pairs, drawing each estimate from that country’s own stratified-PSU bootstrap, puts the thresholds at ≈ 0.033 (net) and ≈ 0.075 (persistent), with realized size 0.001–0.007 against a nominal 0.10: the rule is markedly conservative, and non-certification is weak evidence of absence at every rung (e42). The powered instrument for secular decline is the net rung, which Section 7 co-headlines.




Figure 1: Coverage of a whole country trajectory, by the unit the score is attached to (4,000 replicates, nominal 90%). The gap widens with the length of the trajectory being claimed about.

Validation, in three disclosed layers. A first sealed holdout (450 cells) is labelled *development*, because an audit found its scorer evaluated the S2 studentized band rather than the deployed one, and its findings motivated the switch to U0 and the Theorem 5 architecture. A corrected-scorer rerun of the same grid scores the deployed band verbatim: all 450 cells floor-compatible, worst 0.882, deconvolution active only at $K = 320$. Because both layers had touched the final design, we sealed one further validation on six new DGP families, script hash recorded before first execution and reported as produced including a disclosed first-seal generator bug (e33): 120/120 floor-compatible, worst 0.878, zero activations below $K = 94$ as the floor requires. The audit trail is in the Supplementary Material.

A design-preserving stress test, and what it does not show. Subsampling the real AmericasBarometer, the deployed selector never fires, and the pooled $\hat{\rho}$ turnover at deep subsampling coincides with ≈ 1 PSU per stratum, where the m -of- m variance estimate collapses. The sweep therefore demonstrates a failure mode of the $\hat{\rho}$ diagnostic under sparse-PSU designs, not a saturation law; Section 6’s regime characterization rests on full-sample

estimates instead (Supplementary Material).

6 Evidence from the ESS and the AmericasBarometer

The regime characterization. On real data the selector reduces to clustered conformal, and the reason is worth stating. Across both surveys, both estimands, and three outcomes, cross-national inference is a uniformly *low design-noise* regime: $\hat{\rho} \leq 0.22$ on LAPOP, at most 0.29 in the ESS subgroup scan, well below the $\rho_0 = 0.47$ cutoff. Every $\hat{\rho}$ we report is a downward-biased *floor*, because the PSU bootstrap resamples *m-of-m* without Rao–Wu–Yue rescaling (Rao et al., 1992) and single-PSU strata contribute no variance. The rescaled rerun confirms the floors are tight: maxima 0.281 (ESS) and 0.222 (LAPOP), still severalfold below ρ_0 , zero gate activations, every certification count unchanged; and singleton strata, which no rescaling repairs, are 1 of 7,028 in the core rounds. The safe selector thus reduces to clustered PCB on all real data, not by assumption but by its own low- ρ gate.

Why the deconvolution is unreachable, precisely.

Proposition 1 (Survey-scale unreachability). *The deployed selector activates deconvolution only if a need gate $\hat{\rho}_{\text{LCB}} > \rho_0$ and a reliability gate $D \leq \tau_D$ both hold, $D = \max_t \widehat{\text{SE}}(\hat{s}_T^2)/\hat{s}_T^2$. Both are bounded by algorithmic identities of the frozen procedure. (a) $\rho = \sqrt{v^2}/s_{\text{plug}} \in [0, 1)$ with $s_{\text{plug}}^2 = s_R^2 + \overline{v^2}$: the need gate fires only when design noise is an appreciable fraction of the between-population signal. (b) Since $\hat{s}_T \leq s_{\text{plug}}$ by construction, $D \geq \sqrt{2/(K-1)}$, so the reliability gate requires $K \geq 1 + 2/\tau_D^2$, i.e. $K \geq 94$ at the frozen $\tau_D = 0.147$. (Appendix A separates the deterministic statement from its kurtosis-dependent interpretation.)*

The two requirements pull apart on real surveys (Figure 2). On the ESS the noisiest subpopulations raise $\hat{\rho}$ only to 0.29 while $K \leq 33$ leaves $D \geq 0.25$: neither gate opens (42 cells, zero activations). The WVS is the mirror image: its full item-coverage sets ($K = 95$ –105) make the reliability gate feasible, the certification samples ($K = 59$ –77) do not, and in

either denominator the weights-only $\hat{\rho}_{\text{LCB}} \leq 0.09$ fails the need gate decisively. The survey large enough to estimate the deconvolution has almost no design noise to remove; the survey with real clustered noise has far too few countries.

Where the correction does live: small areas, on this same survey. The barrier is about the unit, and the ESS itself contains a finer one. Take the estimand this regime is actually for, a region’s departure from its own *national* distribution, $D_g = F_g - F_{\text{nation}}$, and calibrate the transport band across regions (e54). A single stratified-PSU bootstrap of the whole country recomputes F_g and F_{nation} on every replicate, so the design SD is that of the difference; the missing-value sentinel and the three countries whose “region” is the country are excluded, and a country needs two usable regions to express a departure at all.

On that estimand the design-to-total ratio is not marginal: $\hat{\rho}_{\text{LCB}}$ runs 0.26–0.52 and clears $\rho_0 = 0.47$ in eight of twenty-three unit-rounds. Reliability needs scale, and the two gates open together only once $K \gtrsim 230$: units of forty to sixty respondents, rounds 9 and 10, $K = 228$ –287. There the *frozen* selector, no constant retuned, activates the design-aware branch for the first time on real survey data: a band 15–17% narrower than the conservative envelope at the reported level 0.881, clearing the efficiency gate by 0.14–0.22 against its 0.10 threshold, across twelve independent bootstrap streams.

Is the region an exchangeable unit? The regions nest in twenty-seven countries, nine each, and between-country differences carry 32–49% of the variance in a region’s sup-departure: the objection this paper would itself raise is that the effective unit is the country and K is really 27. Holding out whole countries answers it (e55). Calibrating on the other twenty-six countries’ regions, the plug-in anchor covers 0.893–0.903 against its 0.900 target in all twelve cells, and, the informative contrast, differs by at most 0.015 from leave-one-*region*-out calibration, which keeps the held-out region’s country-mates. Deleting nine country-mates from the calibration set costs nothing, so within-country dependence does not deflate the quantile. In the activating cells the selected band covers 0.94–0.98 against its nominal 0.88,

scored on the observed departure, hence a lower bound for a branch targeting the latent one. Coverage conditional on the country does not transfer: the median held-out country is fully covered but the tenth percentile is 0.75, the worst three (Bulgaria, Greece, Hungary, 0.53–0.63) being those with the largest regional heterogeneity. The guarantee is marginal over regions, as conformal guarantees are, and we do not read it per country.

Two further scope conditions travel with it. Reaching $K \gtrsim 230$ requires pooling regions coded at different NUTS levels; restricted to the fourteen countries sharing one level the need gate still opens in nine of twenty-one unit-rounds, but $K \leq 140$ keeps the reliability gate shut and the selector falls back to the conservative envelope, the same two-barrier structure as the national result above, one level down. And round 11 never activates, because its regional design noise is lower. The correction is therefore not unreachable in principle, and not reachable across countries: it lives at the small-area scale, which is where Theorem 1’s remark said it would.

How coarse can the calibration unit be? One constraint is sharp and, as far as we know, unremarked: the conformal level is infeasible whenever $K < \alpha^{-1} - 1$, because the required order statistic exceeds the sample and the band is $[0, 1]$ at any width—a too-coarse unit is unusable, not merely inefficient, and the cross-national default clears the floor comfortably ($K = 30$ – 34 against nine). Refining is not free either: with units of a controlled target size built by grouping whole PSUs, the band’s half-width falls monotonically as units coarsen, from 0.190 at forty respondents per unit to 0.065 at three hundred and fifty (e52). Both are statements about the *calibration* unit; an estimand’s unit is fixed by the question, and choosing among substantive areal partitions is the modifiable areal unit problem (Openshaw, 1984; Robinson, 1950), to which we add nothing.




Figure 2: The two barriers at the national unit, and why no survey clears both. Left, $\hat{\rho}$ against ρ_0 by ESS age band (each point the maximum over that band’s min- n sweep, 42 cells). Right, reliability D against its floor $\sqrt{2/(K-1)}$: the ESS sits on the floor at $K \leq 33$, and only the WVS item sets reach $K \geq 94$, where gate A fails instead.

7 Political reanalysis: how many democracies really declined?

We analyze trust in parliament (`trstpr1`) and satisfaction with democracy (`stfdem`) in ESS rounds 9–11 (2018–2024, the window whose integrated files ship PSU/stratum identifiers), then extend every trajectory to the full record (rounds 1–11, 2002–2024), asking at each rung how many countries survive. The comparative literature has grown skeptical of a continent-wide trust decline (Norris, 2017; Voeten, 2017; Wuttke et al., 2022; Valgarðsson et al., 2025); we add a formal instrument that says so and the wrong-unit diagnosis of why the over-reading arises. The dominant trend estimates (Valgarðsson et al., 2025) rest on latent-trait models whose intervals carry no design-based uncertainty layer (Tai et al., 2024) and whose data end where our window begins.

A hierarchy of claims, and one band beneath it. The claims differ in their unit. A *pairwise* claim asks whether some pair of waves shows a distributional shift; *any-pair* aggregates these within a country; *net* asks whether the first-to-last span declined; *persistent*

country-wide asks whether the whole distribution declined simultaneously across the trajectory; *Bonferroni* further controls the number of countries examined. Each rung is strictly stronger than the last, and conflating them is exactly the over-detection this paper is about.

The rungs are not separate tests: each of them, every sub-span, and the reverse direction is a function of one object, the country’s surface of wave-pair contrasts, so all are certified on one coverage event.

Proposition 2 (Claim-family transfer). *Let $\widehat{B}$ be a simultaneous $1 - \alpha$ band for a country’s contrast surface $\theta = \{\theta_{a,b}(t)\}$ over every ordered pair of observed rounds, and let $\{A_j\}$ be any family of claims, each a set of surfaces. Define the certified subfamily $J = \{j : \widehat{B} \subseteq A_j\}$. Then $\Pr(\theta \in A_j \text{ for every } j \in J) \geq 1 - \alpha$, with no dependence on $|J|$: on $\{\theta \in \widehat{B}\}$, set inclusion delivers every certified claim at once.*

The proof is the line just given, and the argument is standard: reading every deterministic consequence off one simultaneous region is the post-hoc logic of Scheffé (1953), closed testing (Marcus et al., 1976), and the selection-free bounds of Goeman and Solari (2011); Katsevich and Ramdas (2020). The contribution is its deployment: trend claims in this literature are made rung by rung, and reading them off a single studentized sup- t band over the whole contrast family removes the corrections a per-rung construction needs: no Bonferroni across a country’s pairs, no separate budget for certified recoveries, and no endpoint-selection cost. The price is a wider critical value, and we report what it costs.

Which instrument certifies what. Within-country *certification* is a design-based simultaneous (sup- t) band on wave-pair CDF differences from the stratified-PSU bootstrap (Rao and Wu, 1988; Wolter, 2007), an asymptotic guarantee in which exchangeability plays no role; the conformal transport band calibrates cross-country prediction and the regime diagnostics. Headline counts are certification counts, and the theory sections’ finite-sample language does not transfer to them.

The counts collapse up the hierarchy. For `trstprl` over rounds 9–11, a marginal pairwise reading flags 20 of 30 countries; an any-pair design-aware band drops this to 12; net first-to-last decline holds in 6 (Austria, Belgium, Estonia, the United Kingdom, Greece, the Netherlands); and the *persistent, design-aware simultaneous* band over the preregistered low-trust core (the strongest rung) certifies one, Greece, which also survives Bonferroni across countries. One disclosure is essential. *Greece fielded only rounds 10 and 11 here*, so its trajectory is a single pair and the top rungs coincide for it (as for Czechia and Israel, which do not certify). Among the 27 two-pair countries none certifies persistence, while the United Kingdom, Belgium, and the Netherlands pass the *plug-in* persistent rung and are demoted by the design-aware layer alone. Both numbers are the headline: net decline in six of thirty, persistent decline in one, and that one on a single pair. The severity analysis (Section 5) explains why: the persistent rung has 80% power only against crisis-scale declines, so its non-certifications are weak evidence of absence. For `stfдем` the pattern repeats (23 marginal, 14 any-pair, 8 net, one persistent: Greece, again one pair, failing Bonferroni there). The literature reads Greece as a crisis-era legitimacy collapse (Armingeon and Guthmann, 2014; Torcal, 2014), but those accounts concern 2009–2015 while the certified pair is 2020/21→2023/24.

The long window: the secular question, asked properly. Extending every trajectory to its full record (rounds 1–11; median six pairs, up to ten; rounds 1–8 weights-only) reframes the twenty-year narrative in both directions (`e36`). Zero of the thirty-three countries with three or more usable rounds certify persistent distribution-wide decline over their full record, plug-in included. The null is not a bare one: reversing the inequality certifies *recoveries*, and across the 1,173 ordered contrasts of the trust series certified movement is directionally balanced (193 declining against 212 rising). Inside the same band, and therefore at the same α for that country, twenty-three of thirty-three countries certify at least one decline and at least one recovery, on each outcome separately and twenty on both (`e50`); the two directions

share one critical value by construction, so no within-country correction is needed. The count across countries is a conjunction of thirty-three separate coverage events and carries no familywise control, as do all the country counts in this section unless the Bonferroni rung is named. Whatever European trust did over two decades, it was not a monotone slide, though we stop short of calling it episodic, which would additionally require same-signed runs and returns toward baseline.

Under Proposition 2—one band, every ordered contrast and both directions at $\alpha = 0.10$ jointly (e50)—net erosion over the whole span certifies in eight countries (Cyprus, Spain, the United Kingdom, Greece, Hungary, Israel, Italy, Ukraine; Table 1). Against the per-rung construction the joint statement costs France at the span rung ($9 \rightarrow 8$) and six countries at the any-pair rung ($28 \rightarrow 22$); the two runs define adjacency differently, and the persistent zero holds under both (Supplementary Material). The under-detection face of the wrong unit shows in the ledger of contrasts: Hungary certifies its 22-year span while only 9 of its 55 ordered contrasts certify, and the United Kingdom 11 of 55, erosion that a reading built from adjacent waves alone would mostly miss. Because every endpoint choice is certified at once, the band also delivers the *share of a country’s ordered contrasts that certify a decline*: a lower bound, comparable within a country but not across (the shared critical value grows with record length, correlation 0.96; the denominator grows quadratically), so we do not rank on it. Within a country it is informative: Spain certifies over 32 of its 55 contrasts and Slovenia over 21 of 55, neither entering the eight because their span contrast happens not to certify, which is the endpoint sensitivity the joint band exposes. Ukraine’s certified span decline of at least 25 points runs from the post-Orange-Revolution wave of 2005 to a wartime sample: a certified statement about those two waves.

The reclassified countries are the weak-signal, higher-noise cases—*certified by the marginal plug-in but inconclusive under the design-aware band*, never “false positives,” a term we reserve for simulation with known truth.

Table 1: Certified net decline in parliamentary trust, 2002–2024, read off one band covering every ordered contrast and both directions at $\alpha = 0.10$ jointly. *Decline* $\geq$: simultaneous lower bound over the preregistered core, in CDF points. *Contrasts*: ordered round pairs certified declining, of all admissible; their share is the endpoint-free erosion index. The certified set is unchanged at any weights-only design effect in $[0.6, 2.0]$.

country	rounds	decline $\geq$	contrasts	share
Ukraine	2–11	25.9	7/15	0.47
Cyprus	3–11	6.2	13/21	0.62
United Kingdom	1–11	6.1	11/55	0.20
Greece	1–11	3.1	8/15	0.53
Israel	1–11	2.6	10/28	0.36
Italy	1–11	1.6	5/15	0.33
Hungary	1–11	1.1	9/55	0.16
Spain	1–11	0.6	32/55	0.58




Figure 3: Certified declines collapse up the hierarchy ($\alpha = 0.10$). Left, rounds 9–11 ($K = 30$), with one path per inference layer; the headline sequence $20 \rightarrow 12 \rightarrow 6 \rightarrow 1$ reads down the plug-in marker and then along the design-aware path. Right, the full record off one joint band ($K = 33$), where the two layers coincide by construction and one path is drawn.

Two confounds this window cannot exclude. Round-10 fieldwork coincided with the pandemic’s rally-round-the-flag movements, so “persistent decline through this window” is a claim made against a rally; and nine countries switched to self-completion at round 10, confounding wave-pair shifts with mode effects, a bias no design bootstrap absorbs. A mode audit built from the data’s own mode variable bounds it: the Greek pair is mode-constant and net counts are unchanged when the switchers’ confounded pairs are excluded, only their any-pair claims being affected. A preregistered age-group analysis likewise finds the result is not an artifact of pooling ages, youth certifying zero persistent declines as an underpowered

null rather than youth stability (Supplementary Material).

A second, global target: Foa–Mounk deconsolidation. We preregistered a reanalysis of the “democratic deconsolidation” thesis (Foa and Mounk, 2016, 2017) on the WVS/EVS trends (1981–2022, 59–77 countries with ≥ 2 waves), recoding the five-item battery so that deconsolidation is a persistent decline over each scale’s preregistered core. The verdict is calibration, not denial, but the surviving phenomenon is not the one the thesis was about. A *marginal wave-pair reading of the same data*, a criterion we construct to instantiate the bottom rung, since Foa and Mounk’s own empirics are cohort comparisons, flags 36–64 countries per item against 6–17 (8–24%) at the persistent rung. That $2.6\text{--}6.5\times$ ratio compounds two changes, and we separate them: holding the inference layer fixed, the rung alone accounts for $1.7\text{--}4.8\times$ (plug-in) or $1.9\text{--}4.8\times$ (design-aware), and propagating design uncertainty at fixed rung accounts for the remainder. The unit is the larger effect, but not the whole of the headline number. Three caveats. The WVS ships no PSU/stratum identifiers, so the weights-only bootstrap understates design variance, which can only *inflate* counts: at variance $\times 1.5$ and $\times 2.0$ the certified core holds at 13 and 12 countries and the gap widens to $3.0\text{--}8.3\times$, so the reported gap is a lower bound. The per-item lists carry no across-country familywise control, so we aggregate to multi-item co-certification before interpreting geography. And the certification sets sit below the $K \geq 94$ bound, so every WVS band uses the full- α anchors of Theorem 5. The youth “embrace authoritarianism” claim is only half-supported (Supplementary Material).

The certified core: where the surviving deconsolidation lives. Aggregating per-item certifications yields a positive characterization (Figure 4; textttte30): of 38 countries certified on ≥ 1 item, 13 form a certified core on ≥ 2 , headed by Albania on four. The core is post-communist and Arab-Spring states with fragile Latin American and African cases alongside, not the mature democracies the thesis (Foa and Mounk, 2016, 2017) concerned, formalizing with per-country error control the decline-from-euphoric-

baselines pattern the post-communist literature described qualitatively (Mishler and Rose, 1997; Inglehart and Catterberg, 2003). Three qualifications travel with it. Five core members are electoral autocracies in the V-Dem classification, where falling stated support reflects autocratic legitimation rather than deconsolidation in the consolidated-democracy sense. The West enters the core exactly twice (Finland and Switzerland, on the strongman/army pair, which we flag as a probable administration artifact), with single-item entries elsewhere: no consolidated Western democracy certifies on support for a democratic system, consistent with Wuttke et al. (2022), though not that the West is absent. And the geography is partly window-contingent: recertifying on fieldwork ending by 2017 (e46) keeps eight of the thirteen but drops all three Arab-Spring cases, so the post-communist component is window-stable and the Arab-Spring component rests on WVS wave 7. Certified attitudes do not forecast institutions: core membership predicts subsequent V-Dem electoral-democracy decline no better than the marginal flag ($n = 13$ versus 54; Fisher $p = 0.89$), too small a comparison to establish the decoupling recent panel work anyway expects (Ouattara and van der Meer, 2023; van der Meer and Janssen, 2025). The estimand is the attitude trajectory itself: certification is descriptive error control, not a forecast. Item-level caveats are in the Supplementary Material.

8 Related work

Four literatures intersect here; the Supplementary Material gives the extended discussion. *Conformal prediction* (Vovk et al., 2005; Lei et al., 2018; Barber et al., 2023): our selector adapts not to temporal shift (Gibbs and Candès, 2021) but to the certified magnitude of survey design noise. *Cluster-as-unit conformal* (Dunn et al., 2023; Lee et al., 2023) transports guarantees to an unseen cluster but treats each cluster’s data as cleanly sampled (the same clustered construction is developed, for a non-survey domain, in a companion paper (Park, 2026)); our departure is that the calibration objects are estimated under complex designs

(Binder, 1983; Lumley, 2010). *Noisy calibration*: Wieczorek (2023) already brings conformal prediction to complex survey designs, for unit-level prediction under design-based inference. Our departure is the simultaneous trajectory object, the population as the exchangeable unit, and the estimated-calibration boundary. Einbinder et al. (2024); Sesia et al. (2025) deconvolve a *known* label-noise model, an identification premise that generally fails for design noise (Theorem 1); and even a supplied noise law faces the finite- K floor (Proposition 1). *Functional simultaneous bands* (Diquigiovanni et al., 2021): unlike FDR/Bonferroni corrections of marginal tests (Benjamini and Hochberg, 1995), the “persistent” object is covered directly by one band, a distinction of estimand, not error rate (Gelman et al., 2012), and the post-hoc logic by which we read a whole claim family off it is classical (Scheffé, 1953; Marcus et al., 1976; Goeman and Solari, 2011; Katsevich and Ramdas, 2020). Substantively we engage the trust-decline and deconsolidation debates (Norris, 2017; Voeten, 2017; Wuttke et al., 2022; Valgarðsson et al., 2025; Foa and Mounk, 2016, 2017; Ouattara and van der Meer, 2023; van der Meer and Janssen, 2025; Kołczyńska and Bürkner, 2026). The closest substantive competitor is Claassen (2019, 2020), whose latent-variable panels model measurement and sampling uncertainty with model-based credible intervals whose calibration is itself contested (Tai et al., 2024). Our bands trade pooling and width for finite-sample, model-free coverage at a stated claim rung, and the two are complements. The certified core’s geography intersects the post-communist disillusionment literature (Mishler and Rose, 1997; Inglehart and Catterberg, 2003), which anticipated the decline-from-euphoric-baselines pattern our certification formalizes per country.

9 Discussion

Uncertainty in claims about repeated cross-national surveys is usually computed for the wrong unit—twice. We gave a multiplicity-honest simultaneous band for the claim unit and a hard boundary for the calibration unit: non-identified without the design-noise law

(Theorem 1), unreachable at cross-national scale with it (Proposition 1). The deployed object is the reduction, a clustered band exact at any K inside a selection-free selector (Theorems 3, 5), and the design-aware layer certifies, rather than corrects, at survey scale.

When it reduces to ordinary conformal. At the national unit the method reduces exactly to clustered population conformal: the machinery certifies that the simple band is the right one here, and reports the ρ that says so. The deconvolution regime needs many exchangeable units and comparable design noise, never both across countries, but reachable one unit down (Section 6) and routine in simulation at many-unit scale (e31: $K \approx 220\text{--}300$ small areas, deconvolution on up to 98% of draws at $0.69\text{--}0.74\times$ the conservative width with valid coverage).

Limitations. Four scope conditions, stated fully in the Supplementary Material. *Sampling error only:* the machinery is silent on measurement non-invariance (wording and translation changes, house effects, mode switches), which produces exactly the shifts the bands certify; certifications straddling such changes are conditional on measurement constancy. *Variance-estimator bias:* the deployed m -of- m PSU bootstrap (Rao et al., 1992; Wolter, 2007) biases design variance downward, though the Rao–Wu–Yue rescaled rerun leaves every count and gate unchanged. *A superpopulation postulate:* transport-band exchangeability is over a non-sampled, panel-attriting country set (the certifications do not use it), and holds worse for the post-communist bloc than elsewhere. *Metadata:* without design metadata (WVS) only weights-only replication is possible.

The general lesson. Attaching uncertainty to the right unit changes substantive conclusions: persistence in none of thirty-three European democracies over two decades yet span erosion in eight, mostly invisible to adjacent-wave readings; a several-fold over-count of persistent deconsolidation, with the surviving core concentrated outside the consolidated West. The pattern is not confined to surveys: wherever prediction is calibrated on estimated

objects: small-area model outputs, learned features, meta-analytic effects (Remark 1), the calibration targets carry their own error, and the claim unit is often coarser than the trend asserted. The right response is not to widen every band reflexively but to state the strongest object the data support, correct the estimation noise when it can be identified, and abstain when it cannot.

A Proofs and efficiency results

Full statements and proofs of all theorems, the efficiency results, and the modulation self-inclusion deficit are in Section S1 of the supplementary material; each theorem is paired with a machine-checked contract test.

B Frozen selector specification

The frozen constants, their development-grid derivation, and the validation protocols are in the replication package.

Acknowledgments

The author used AI assistance in preparing parts of the analysis code and in revising proof arguments; a full disclosure follows the journal’s generative-AI policy. All AI-assisted output was reviewed and verified by the authors, who takes full responsibility for the content of this article.

Competing Interests

Competing interests: the author declares none.

Corresponding Author

Kunwoo Park, Department of Politics, Kookmin University, Seoul, Republic of Korea; pkw31386094@gmail.com.

Data and Code Availability

Simulation, theory, and benchmark results are deterministic under fixed seeds with no external data, and each theorem is paired with a machine-checked contract test. The ESS, World Values Survey, and AmericasBarometer/LAPOP microdata are licensed to their providers and not redistributed; the replication package documents the exact variables, waves, and retrieval steps, and will be deposited in the Political Analysis Dataverse upon conditional acceptance.

References

- Armington, K. and K. Guthmann (2014). Democracy in crisis? the declining support for national democracy in european countries, 2007–2011. *European Journal of Political Research* 53(3), 423–442.
- Barber, R. F., E. J. Candès, A. Ramdas, and R. J. Tibshirani (2023). Conformal prediction beyond exchangeability. *The Annals of Statistics* 51(2), 816–845.
- Benjamini, Y. and Y. Hochberg (1995). Controlling the false discovery rate: a practical and powerful approach to multiple testing. *Journal of the Royal Statistical Society Series B* 57(1), 289–300.
- Binder, D. A. (1983). On the variances of asymptotically normal estimators from complex surveys. *International Statistical Review* 51(3), 279–292.
- Claassen, C. (2019). Estimating smooth country-year panels of public opinion. *Political Analysis* 27(1), 1–20.

- Claassen, C. (2020). Does public support help democracy survive? *American Journal of Political Science* 64(1), 118–134.
- Cohen, M. J., N. Lupu, and E. J. Zechmeister (2021). The political culture of democracy in the americas, 2021: Taking the pulse of democracy. Technical report, LAPOP, Vanderbilt University. AmericasBarometer.
- Diguiovanni, J., M. Fontana, and S. Vantini (2021). Conformal prediction bands for multivariate functional data. *arXiv preprint arXiv:2106.01792*.
- Dunn, R., L. Wasserman, and A. Ramdas (2023). Distribution-free prediction sets for two-layer hierarchical models. *Journal of the American Statistical Association* 118(544), 2491–2502.
- Einbinder, B.-S., S. Bates, A. N. Angelopoulos, A. Gendler, and Y. Romano (2024). Label-noise robustness of conformal prediction. *Journal of Machine Learning Research* 25. arXiv:2209.14295.
- Foa, R. S. and Y. Mounk (2016). The democratic disconnect. *Journal of Democracy* 27(3), 5–17.
- Foa, R. S. and Y. Mounk (2017). The signs of deconsolidation. *Journal of Democracy* 28(1), 5–15.
- Gelman, A., J. Hill, and M. Yajima (2012). Why we (usually) don’t have to worry about multiple comparisons. *Journal of Research on Educational Effectiveness* 5(2), 189–211.
- Gibbs, I. and E. Candès (2021). Adaptive conformal inference under distribution shift. In *Advances in Neural Information Processing Systems*, Volume 34.
- Goeman, J. J. and A. Solari (2011). Multiple testing for exploratory research. *Statistical Science* 26(4), 584–597.

- Gupta, C., A. K. Kuchibhotla, and A. Ramdas (2022). Nested conformal prediction and quantile out-of-bag ensemble methods. *Pattern Recognition* 127, 108496.
- Inglehart, R. and G. Catterberg (2003). Trends in political action: The developmental trend and the post-honeymoon decline. *International Journal of Comparative Sociology* 43(3-5), 300–316.
- Kaminska, O. and P. Lynn (2017). Survey-based cross-country comparisons where countries vary in sample design: issues and solutions. *Journal of Official Statistics* 33(1), 123–136.
- Katsevich, E. and A. Ramdas (2020). Simultaneous high-probability bounds on the false discovery proportion in structured, regression and online settings. *Annals of Statistics* 48(6), 3465–3487.
- Kołczyńska, M. and P.-C. Bürkner (2026). Does political trust strengthen democracy? a cross-national longitudinal analysis. *International Political Science Review*. OnlineFirst, doi:10.1177/01925121251405191.
- Lee, Y., R. F. Barber, and R. Willett (2023). Distribution-free inference with hierarchical data. *arXiv preprint arXiv:2306.06342*. Forthcoming, ACM/IMS Journal of Data Science.
- Lei, J., M. G’Sell, A. Rinaldo, R. J. Tibshirani, and L. Wasserman (2018). Distribution-free predictive inference for regression. *Journal of the American Statistical Association* 113(523), 1094–1111.
- Lumley, T. (2010). *Complex Surveys: A Guide to Analysis Using R*. Wiley.
- Marcus, R., E. Peritz, and K. R. Gabriel (1976). On closed testing procedures with special reference to ordered analysis of variance. *Biometrika* 63(3), 655–660.
- Mishler, W. and R. Rose (1997). Trust, distrust and skepticism: Popular evaluations of civil and political institutions in post-communist societies. *The Journal of Politics* 59(2), 418–451.

- Norris, P. (2017). Is western democracy backsliding? diagnosing the risks. HKS Faculty Research Working Paper RWP17-012, Harvard Kennedy School; Journal of Democracy web exchange. SSRN 2933655.
- Openshaw, S. (1984). *The Modifiable Areal Unit Problem*. Number 38 in Concepts and Techniques in Modern Geography. Norwich: Geo Books.
- Ouattara, E. and T. van der Meer (2023). Distrusting democrats: A panel study into the effects of structurally low and declining political trust on citizens’ support for democratic reform. *European Journal of Political Research* 62(4), 1101–1121.
- Park, K. (2026). Honest uncertainty for transported social indicators: Simultaneous confidence bands for poverty curves under population shift. Working paper. Develops the same finite-sample-exact clustered construction for a non-survey domain.
- Rao, J. N. K. and C. F. J. Wu (1988). Resampling inference with complex survey data. *Journal of the American Statistical Association* 83(401), 231–241.
- Rao, J. N. K., C. F. J. Wu, and K. Yue (1992). Some recent work on resampling methods for complex surveys. *Survey Methodology* 18(2), 209–217.
- Robinson, W. S. (1950). Ecological correlations and the behavior of individuals. *American Sociological Review* 15(3), 351–357.
- Scheffé, H. (1953). A method for judging all contrasts in the analysis of variance. *Biometrika* 40(1-2), 87–110.
- Sesia, M., Y. X. R. Wang, and X. Tong (2025). Adaptive conformal classification with noisy labels. *Journal of the Royal Statistical Society Series B* 87(3), 796–815.
- Tai, Y. C., Y. Hu, and F. Solt (2024). Democracy, public support, and measurement uncertainty. *American Political Science Review* 118(1), 512–518.

- Torcal, M. (2014). The decline of political trust in spain and portugal: economic performance or political responsiveness? *American Behavioral Scientist* 58(12), 1542–1567.
- Valgarðsson, V., W. Jennings, G. Stoker, H. Bunting, D. Devine, L. McKay, and A. Klassen (2025). A crisis of political trust? global trends in institutional trust from 1958 to 2019. *British Journal of Political Science* 55. Article e15.
- van der Meer, T. W. G. and L. A. Janssen (2025). Pushing and pulling: The static and dynamic effects of political distrust on support for representative democracy and its rivals. *Political Behavior* 47(3), 1389–1411.
- Voeten, E. (2017). Are people really turning away from democracy? *Journal of Democracy* web exchange. SSRN 2882878.
- Vovk, V., A. Gammerman, and G. Shafer (2005). *Algorithmic Learning in a Random World*. Springer.
- Wieczorek, J. (2023). Design-based conformal prediction. *Survey Methodology* 49(2). Statistics Canada, Catalogue No. 12-001-X. arXiv:2303.01422.
- Wolter, K. M. (2007). *Introduction to Variance Estimation* (2nd ed.). New York: Springer.
- Wuttke, A., K. Gavras, and H. Schoen (2022). Have europeans grown tired of democracy? new evidence from eighteen consolidated democracies, 1981–2018. *British Journal of Political Science* 52(1), 416–428.
- Yang, Y. and A. K. Kuchibhotla (2024). Selection and aggregation of conformal prediction sets. *Journal of the American Statistical Association* 119(545), 435–447.




Figure 4: Co-certification across the five battery items (WVS/EVS 1981–2022; $K = 59\text{--}77$ per item). Countries above the dashed line form the ≥ 2 -item certified core.